


About Us

Mint Energy develops energy generation and energy storage solutions to meet the ever-changing needs of modern-day consumers and businesses. Mint Energy strives to provide safe, environmentally-friendly, cost-effective, and reliable solutions.



Solar In A Box

- Efficient energy generation & storage
- Containerized system
- Battery in container
- Fast deployment
- Scalable solution
- Environmentally-friendly
- Storm proof - just push back inside



Power. 440 KWh per day included



Storage. 436 KWh included



Scalable. Distribution of 120V, 220V, & 230V



Fast Deployment. Deploys in 1 day



Mobile. Set-up and teardown as needed



Contact us



+1 949 432-9091



sales@mintenergy.com



895 Dove Street Suite 300
Newport Beach, CA 92660 USA



www.mintenergy.com

MODEL	SolarBox 20' 82.5KWP	
RATED POWER	PV Solar Capacity	82.5 kWP (150x550W)
	Typical daily energy output from PV solar	200-400kWh
	AC Output	60kW continuous
SYSTEM	Operation mode	On-grid/Off grid – Automatic Island mode (Built in ATS) Microgrid mode, parallel up to 10x containers with NODE MODULE (Optional)
ENERGY STORAGE (DC INPUT/OUTPUT)	Nominal voltage	270 Vdc
	DC voltage range	205 - 300 Vdc
	Battery Type	Graphene
	Battery capacity	126 kWh (10x12.6kWh)
	Minimum / Maximum charge voltage	235 Vdc / 297 Vdc
	Maximum charging current	500 A @ 240 Vdc
	Maximum discharging current	250 A
	Max. charging power Max. discharging power	120 kW (80 kW from PV + 40kW from grid or generator) 60 kW
AC INPUT FROM UTILITY GRID OR DIESEL GENERATOR	Voltage	380 / 400 /415 Vac (L-L), 220 / 230 / 240 Vac (L-N)
	Phase	Three phase four wires
	Frequency	50 / 60 Hz \pm 2 Hz
	Acceptable input voltage range	360 - 480 (L-L)
	Maximum AC input current	90 A @ 400 Vac
	Input connections (ATS Based)	1x125A Breaker (Grid) 2x125A breaker (2xGenerator) optional CEE Plugs
AC OUTPUT	Voltage	380 / 400 / 415 Vac (L-L), 220 / 230 / 240 Vac (L-N)
	Voltage regulation	\pm 3 % (steady load), < 7% at 100% step load within 0.1 sec.
	Phase	Three phase four wires
	Frequency	50 / 60 Hz
	Wave form	Pure sine wave
	Nominal output current	90 A @ 400 Vac
	Power factor	0.99
	Total harmonic distortion	THDi < 3%
	Maximum surge current	200%
	Maximum output current	90 A @ 400 Vac
Output connections	1x125A Breaker @ 3 Phase 400 Vac (Optional distribution panel with ground fault, breakers and CEE Plugs 1x50A 3 Phase and 6x16A Single Phase)	
EFFICIENCY	Peak efficiency	> 96%
POWER CONSUMPTION	Standby mode	60 W
	Idle mode	520 W
REACTION TIME	Standby to idle mode	3 seconds
	Time to full power (from idle)	12 milliseconds
INDICATOR	LED	Operation Status
	LCD display	Inverter (V/A/Hz/W), AC input (V/A/Hz/W), Battery (V/A/SOC%), Accumulated energy data. System status, Time, Date, Heat sink temperature, Data log, Event log
COMMUNICATION	Communication port	Local RS-485 and RJ45 to internet/cloud services
INTERFACE	Protocol	MODBUS
ENVIRONMENT	Temperature	0 to 55°C (Power draining above 50°C)
	Relative humidity	0 - 90 % (non - condensing)
	Maximum operating altitude	2,000 m
DESIGN	Standard	IEC 61727, IEC 62116, IEC 62109-1, IEC 62109-2, UN38.3, TF331
REGULATION	Ingress protection	IP 65
	Protective class	I
DIMENSION	Container	20' HQ Type
	Size (W x H x L in meters)	6.06 x 2.44 x 2.90
	Weight	About 22,000 kgs
	Deployed foot print in meters	6x136 meters (816SQM)

Included in the kit

Part Name	Qty
GTP 4020KW AC connected Inverter	1
String Combiner Box (for GTP)	2
String Combiner Box (for SCC) string level	1
SCU with LCD	1
Smart Power Meter	1
MBMS	1
Bidirectional Inverter 60KW	1
Solar Charge Controller 20.6KW	2
AC Distribution Box	1
Battery Rack + DNH	2
Graphene Battery Module 369Kwh	22
System Assembly	1
PV Cables roll of 100 meter	12
PV MC4 connectors set of 2	100
FAT	1
Climate Control System (EU)	1
Fire Detection and suppression System	1
Various Inverter mount etc	1
ECO DELTA 550w Shingled Panel	150
Container	1
Panel Frames for 3 panels	50
PV panel SS304 M6x15 Bolt+Lock Nut	1200
Wheels 80mm + Bush	52
Wheel frame	52
(HDG) Bolt+Nut for fitting the wheel M12	104
(HDG) Bolt+Nut for fitting the wheel M12	52
Rails 90*45	114
Rail Base/Feet (Landing Leg)	126
AC Winch	1
Upper winch motor support mount	1
Steel wire 8 mm *125 meter	1
SUS Turn Buckle	50
Support bracket for PV Panel	300
Cables	2100
Panel Mount Job	1
wire lock sus	24
Top Hinge	25
Fairleas and Winch Setting Unit	1



Pricing

\$0.29 USD per kWh with a min of 5 hours per day of production

Total minimum payment: \$16,051.00 USD per month for a period of 20 years

Assumes:

- Solar Index of 4
- Production: 330 KWh per day
- Storage: 370 KWh maximum per day

Contact us



+1 949 432-9091



sales@mintenergy.com



895 Dove Street Suite 300

Newport Beach, CA 92660 USA



www.mintenergy.com

